

# VAISHAL PATLIPUTRA DUGDH UTPADAK SAHKARI SANGH LTD

## PATNA DAIRY PROJECT

Feeder Balancing Dairy Complex, Phulwarisharif, Patna – 801505

An ISO 22000:2005 Certified Organisation

Phone 0612-2252553, 2252542, 2251622, Fax 2250325

E.mail: vpmu.pur@gmail.com

GST no. 10AAAV8463B1ZV

### Short Tender Notice

#### *Reminder*

PDP: PUR: FBD: 2605

Dated: 24.06.2025

Sealed tenders are invited from civil contractors registered with Building Construction works Department, Rural Works Department, Water Resource Department, Government of Bihar OR registered with COMFED in suitable class for the civil work as given below :-

Sl no.	Name of Work	Estimated Cost (In Rs.)	Amount of EMD (In Rs.)	Cost of BOQ ( In Rs.)	Time of Completion
	<b>Civil construction works of Foundation for Installation of Cooling Tower at BMC, Paliganj, Patna</b> The details scope of work as per BOQ attached herewith	60,762.00	1215.00	500.00	30 days

- (1) Tender document can be obtained from the Cashier at office (Patna Dairy Project), VPDUSS Ltd during office hours OR it may be downloaded from website – [www.patnadairy.org](http://www.patnadairy.org) up to **02.07.2025 at 3.00 pm**. Downloaded BOQ must be accompany with DD of BOQ Cost. DD of any nationalized bank shall be submitted in favour of “**Vaishal Patliputra Dugdh Utpadak Sahkari Sangh Ltd.**”, Payable at **Patna**
  - (2) Contractors who down load the tender and those who purchase the **tender / BOQ** directly from office at Patna Dairy Project, both will send their completed tender in a sealed envelope **through registered post or through courier to Purchase section at Patna Dairy Project address.**
  - (3) Last date of receipt of completed tender – **03.07.2025 up to 3:00 pm. Tenders received after due date & time shall not to be considered.**
  - (4) Date of **opening all received tenders-04.07.2025 at 3:00pm** in the presence of the tenders of their authorized agent in the office of Patna Dairy Project, VPMU.
  - (5) Tenders received after due date & time shall not be considered.
- Undersigned reserves the right to extend the dates OR cancel the tender.

  
Managing Director

ANNEXURE-01						
BOQ for Civil Construction Work of Foundation for Installation of Cooling Tower at BMC, Paliganj, Patna. (SOR-22 effective from 01-01-2022).						
Sl. No.	SOR Code No	Item Descriptions	Unit	Qty.	Rate	Amount
1	2.8	Earth work in excavation in foundation trenches or drains(not exceeding 1.5 m in width or 10 sqm on plan including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m	cum	4.778	360.70	₹ 1,723.51
2	5.1.3	Providing and laying in position specified grade of reinforced cement concrete excluding the cost of centring,shuttering,finishing and reinforcement-All work upto plinth level 1:1:5:3(1 cement: 1.5 coarse sand:3 graded stone aggregate 20 mm nominal size)	cum	2.079	4,688.30	₹ 9,748.66
3	5.2.2	Reinforced cement concrete work in wall (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts, etc. upt floor five level excluding cost of centring, shuttering, finishin and reinforcement. 1:1:5:3(1 cement: 1.5 coarse sand:3 graded stone aggregate 20mm nominal size)	cum	0.697	5,670.00	₹ 3,951.76
4	11.72	Providing designation 100 A one brick flat soling joints filled with local sand including cost of watering, taxes, royalty all complete as per building specification and direction of E/l.	sqm	5.638	283.30	₹ 1,597.36
5	5.22.7	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete.				
	5.22.7A	Thermo-Mechanically Treated bars TMTC-500-8mm dia	KG	27.176	94.50	₹ 2,568.13
	5.22.7B	Thermo-Mechanically Treated bars TMTC-500-12mm dia.	KG	99.918	92.60	₹ 9,252.38
6	5.9	Centring and shuttering including strutting,propping etc. and removal of form for:				
	5.9.5	Lintels, beams, plinth beams, griders, bressumers and contilevers.	sqm	3.277	404.70	₹ 1,326.12
	5.9.6	Columns,Pillars, Piers, Abutments, Posts and Strut	sqm	8.890	494.40	₹ 4,395.02
7	13.11.3	Cement plaster in course sand 12 mm cement plaster of mix: 1:5(1 cement: 5 coarse sand)	sqm	11.422	146.80	₹ 1,676.81
8	10.16	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete				
	10.16.1	Hot finished welded type tubes C channel (100 mm x50 mm x 4 mm)	Kg.	88.000	123.90	₹ 10,903.20
Total (A)						₹ 47,142.96
8	Carriage of Material					
	i	Stone Chips	cum	2.360	3287.46	₹ 7,757.98
	ii	Coarse Sand	cum	1.356	1143.05	₹ 1,549.92
	iii	Local Sand	cum	0.000	262.77	₹ 0.00
	iv	Bricks	per1000	169.152	1053.35	₹ 178.18
	v	Cement & Steel	MT	1.067	492.75	₹ 525.52
Total (B)						₹ 10,011.61

*Aditya Saurav*



Sl. No.	SOR Code No	Item Descriptions	Unit	Qty.	Rate	Amount
9		Difference in Cost of Materials				
	( i )	Bricks	per1000 nos	169.152	1590.97	₹ 269.12
	( ii )	Cement	MT	0.939	262.78	₹ 246.86
					Total (C)	₹ 515.97
					Total (A+B+C)	₹ 57,670.54
		Add 5.36% as per PWD Govt. of Bihar notification for extra GST 12% to 18%				₹ 3,091.14
					Total	₹ 60,761.68
					Say	₹ 60,762.00
In Words : INR Sixty thousand seven hundred and sixty two only with GST.						
S.NO.	I AM AGREE TO DO THIS WORK		IN %		IN WORDS	
1	ON THE BOQ RATE					
2	BELOW THE GIVEN RATE IN %					
3	ABOVE THE GIVEN RATE IN %					
Signature of contractor with seal			<div>Manager (Engg.)</div>			

Aditya Gaurav