

VAISHAL PATLIPUTRA DUGDH UTPADAK SAHKARI SANGH LIMITED
(Patna dairy Project)
Feeder Balancing dairy Complex, PHULWARISHARIF, Patna, 801505
(Phones: 2252553, 2252542, 2251622, Fax: 0612- 2250 325)
E-Mail -vpmu.engg@gmail.com
GST no - 10AAAV8463B1ZV

Tender Notice

VPMU: ENGG: CIVIL: FBD: 1510

Date: 25/05/2026

1. Sealed tenders are invited for the following works from contractors registered with the Building Construction Department/Rural Works Department/Water Resources Department under government of Bihar or registered with COMFED under the appropriate category. Contractors registered with departments other than COMFED must, at the time of purchase of the Bill of Quantities, submit evidence that they have completed at least two separate similar works of the same nature within the last four years, costing the same or more than the work for which they are tendering. In the absence of this evidence, Bill of Quantities will not be issued.
2. Tender document, Bills of quantities can be purchased from the office of the Manager (Engg.), VPMU/ website (www.patnadairy.org) till 3:00 PM upto 17.06.2026. The value/cost of the bill of quantities downloaded from the website will be in the form of a demand draft payable in the name of VAISHAL PATLIPUTRA DUGDH UTPADAK SAHKARI SANGH LTD., PATNA. Tenders will be accepted only if Contractors who download the tender and those who purchase the tender/BOQ directly from office of Manager (Engg.), both will send their completed tender in a sealed envelope through registered post sent by registered post or courier. The last date for submission of tenders is 18.06.2026 till 3:00 PM.
3. Received tenders will be opened in the presence of the Tenderer or his representative on 18.06.2026 at 3:30 PM. VPMU, Patna will not be responsible for late tenders. Contractors other than COMFED registered contractors must attach all documents such as copy of GST registration certificate, copy of PAN registration certificate, copy of payment certificate, Copy of Up to date income tax clearance certificate (ITR) of last three (3) years duly attested by a gazetted officer along with the tender form, otherwise the tender will not be considered.
4. Tender may be rejected if the rate quoted in price part is more than above 10% or more than below 10 % of the estimated rate. VPMU, Patna reserves the right to extend the date or cancel the tender.

<u>S.I. NO.</u>	<u>Name of work</u>	<u>Estimated cost (In Rs.)</u>	<u>Amount of EMD (In Rs.)</u>	<u>Cost of BOQ (In Rs.)</u>	<u>Time of completion</u>
1.	Civil construction work of new MMP (Mineral Mixture Plant) in cattle feed plant at jagdeopath under Patna Dairy Project, Patna .	7,23,504.00	14,471.00	1,250.00	2 months



Managing Director
V.P.M.U, Patna

VAISHAL PATLIPUTRA DUGDH UTPADAK SAHKARI SANGH LIMITED

(Patna dairy Project)

Feeder Balancing dairy Complex, PHULWARISHARIF, Patna, 801505


(Phones: 2252553, 2252542, 2251622, Fax: 0612- 2250 325)

E-Mail -vpmu.engg@gmail.com

GST no - 10AAAV8463B1ZV

1. Sealed tender on prescribed B.O.Q to be eventually drawn in P.W.D. Form- F2 will be received from the Registered Contractors of Building Construction Dept Govt. of Bihar/ RWD/ Water Resources Department, Govt. of Bihar & COMFED up to **18.06.2026 PM till 3.00 PM** by the Manager (Engg.), **VAISHAL PATLIPUTRA DUGDH UTPADAK SAHKARI SANGH LTD., PATNA** for the work of **civil construction work of new MMP (Mineral Mixture Plant) in cattle feed plant at jagdeopath under Patna Dairy Project, Patna** and will be opened in the presence of the Tenderer or their authorized agents on **18.06.2026 at 3.30 PM.**
2. Tenderer should complete the work within **two months** commencing from the date of receipt of written order to commence the work.
3. Tenderer are requested to deposit earnest money at the rate of Rs. 100/- (One hundred) for every Rs. 5000/- or part on the amount of estimate. The earnest money is to be deposited in shape of NSC duly pledged in favor of **VAISHAL PATLIPUTRA DUGDH UTPADAK SAHKARI SANGH LTD.** or Bank Draft in favor of the **VAISHAL PATLIPUTRA DUGDH UTPADAK SAHKARI SANGH LTD.** will also be accepted.
4. The plan, elevation and specification for the work can be seen at the officer of the Manager (Engg.) during the working hour and day.
5. All other information can be obtained on application from the undersigned.
6. The authority reserves the right to reject any or all the tender received without assigning any reason there-of.
7. The earnest money of the successful Tenderer which accompanies the tender will be forfeited in case he (Tenderer) declines to sign. The agreement/contractor to deposit balance security within ten days of being called upon to do so after the acceptance of his tender.
8. The amount of estimate is **Rs. 7,23,504.00 (Rs. Seven Lakh Twenty Three Thousand Five Hundred and Four only).**
9. The rates should be inclusive of all materials. The Tenderer should also indicate the rebate they will allow if levy cement @ Rs. **Nil** per bag either in full or part is arranged for the work.
10. The bill of quantity for the work can be obtained as per tender notice from the office of the Manager (Engg.) during working hours and days on payment of Rs. **1,250.00** (non refundable).EMD and cost of tender shall be enclosed with tender in a sealed envelope.
11. For obtaining BOQ directly contractors shall make a request to Manager (Engg.) who will forward the same to Manager (A/C), FBD for deposition of cost of tender, thereafter BOQ will be issued by Manager (Engg.).
12. Up to date Income tax clearance certificate (ITR) of last three years & other documents as per tender notice should be attached with tender other- wise it is liable to be rejected. Contractors shall submit the acceptance of all the terms & conditions of the tender on their letter head with signature & seal along with the tender form.
13. The contractor must submit copy of his registration no. /category of Registration and office in which registered distinctly.
14. The Tenderer should furnish his full postal address so that any letter at his given postal address will be deemed to have been received by him.

Signature of Contractor


Manager (Engg.)
V.P.M.U, Patna

Estimate / BOQ

Civil Construction work of new Mineral Mixture Plant in Cattle Feed Plant at Jagdeopath Under Patna Dairy Project, Patna

Sl. No	Ref. BSR-2022	DESCRIPTION	Quantity	Unit	Rate (Rs.)	Total Amount (Rs.)
1	15.3	Demolishing R.C.C. work including stacking of steel bars and disposal of unserviceable material within 50 metres lead:	22.600	CUM	1411.20	31,893.12
2	15.56	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	58.80	SQM	21.70	1,275.96
3	15.28.2	Dismantling roofing including ridges, hips valleys and gutters etc. and stacking the material within 50 metres lead of : Asbestos Sheet	200.00	SQM	31.90	6,380.00
4	2.28	Supplying and Filling in plinth with local sand and under floors including, watering, ramming consolidating and dressing complete.	14.45	CUM	287.30	4,150.05
5	11.72	Providing designation 100 A one brick flat soiling joints filled with local sand including cost of watering, taxes, royalty all complete as per building specifications and direction of E/I	144.45	SQM	283.30	40,922.69
6	5.1.2	Providing and laying in position specified grade of reinforced cement concrete excluding the cost of centring, shuttering, finishing and reinforcement-All work upto plinth level : 1:1.5:3(1 cement: 1.5 course sand:3 graded stone aggregate 20 mm nominal size)	21.67	CUM	4688.30	1,01,583.74
7	5.33B.1	Add or deduct for providing richer or leaner mixes respectively at all floor levels : Providing M-25 grade R.C.C. instead of M-20 grade R.C.C.	21.67	CUM	164.50	3,564.30
8	13.11.2	Cement plaster in course sand : 12 mm cement plaster of mix: 1:4(1 cement: 6 coarse sand)	203.25	SQM	152.90	31,076.93
9	13.26	Neat Cement Punning	140.89	SQM	40.50	5,706.05
10	5.22.7A	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete. Thermo-Mechanically Treated bars TMTC-500-8mm dia.	765.52	KG	94.50	72,341.64
11	10.6.1.	Supplying and fixing rolling shutters of approved make, made of required size of M.S. laths inter locked together through their intire length and jointed together at the end by end locks mounted on specially designed pipe shaft with brackets, side guides and arrangements for inside and outside locking with push and pull operation complete including the cost of providing and fixing necessary 27.5 cm long wire springs grade no. 2 and M.S. top cover of required thickness for rolling shutters. : 80x1.25mm thick M.S. laths with 1.25 mm thick top cover.	5.06	SQM	2673.70	13,528.92
12	10.7	Providing and fixing ball bearing for rolling shutters	5.06	SQM	424.20	2,147.51

Aditya Prasad

Ravi

Sl. No	Ref. BSR-2022	DESCRIPTION	Quantity	Unit	Rate (Rs.)	Total Amount (Rs.)
13	11.36	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS:15622(thickness to be specified by the manufacturer) of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge in skirting, risers of steps and dados over 12mm thick bed of cement Mortar 1:3(1 cement: 3 coarse sand) and jointing with grey cement slurry @ 3.3 Kg per sqm including pointing in white cement mixed with pigment of matching shade complete.	51.60	SQM	795.00	41,022.00
14	12.50	Providing and fixing precast galvanized iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purins, rafters and trusses and including cutting to size and shape wherever required.	215.68	SQM	625.10	1,34,824.63
15	12.51.1	Providing and fixing precast galvanized steel sheet roofing accessories 0.50mm (+0.05%) total coated thickness, Zinc coating 120 grams per sqm as per IS:277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester topcoat 15- 18 microns using self drilling / self tapping screws complete Ridges plain (500 - 600mm)	12.00	SQM	396.80	4,761.60
16	13.78.1	Applying one coat of cement primer of approved brand and manufacture on wall surface: Cement Primer	368.98	SQM	38.60	14,242.54
17	13.92.1	Wall painting with plastic emulsion paint of approved brand and manufacture to give an even shade: Two or more coats on new work	368.98	SQM	86.40	31,879.68
18	13.94.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture	147.57	SQM	116.50	17,192.20
19	14.5.1	Renewing glass panes, with putty and nails wherever necessary including racking out the old putty: Float glass panes of thickness 4 mm	14.16	SQM	723.80	10,249.01
Total = A						₹ 5,68,743.72

Aditya Sawary

Kol

Sl. No	Ref. BSR-2022	DESCRIPTION	Quantity	Unit	Rate (Rs.)	Total Amount (Rs.)
20						
CARRIAGE OF MATERIALS						
20.1	N.S.	Bricks for 8 Km	4333.50	per 1000	1053.35	4,564.69
20.2	N.S.	Stone Aggregate for 200 Km	19.28	cum	4371.21	84,294.74
20.3	N.S.	Coarse Sand for 180 Km	12.77	cum	1258.32	16,068.74
20.4	N.S.	Cement for 5 km	14.77	MT	518.09	7,654.52
20.5	N.S.	Steel for 5 km	0.77	MT	518.09	398.92
Total = B						₹ 1,12,981.61
21						
DIFFERENCE IN COST						
21.1	N.S.	Bricks	4333.50	per 1000	357.74	1550.27
21.2	N.S.	Cement	14.77	MT	231.56	3421.19
Total = C						4,971.45
Total A + B + C						₹ 6,86,696.78
Add GST 5.36 %						36,806.94
G. Total						₹ 7,23,503.72
Say						₹ 7,23,504.00
IN WORDS : INR SEVEN LAKH TWENTY-THREE THOUSAND FIVE HUNDRED FOUR ONLY						

		I AM AGREE TO DO THIS WORK	IN %	IN WORD
1		ON THE BOQ RATE		
2		BELOW THE GIVEN RATE (in %)		
3		ABOVE THE GIVEN RATE (in %)		

SIGNATURE OF CONTRACTOR

SIGNATURE OF MANAGER (ENGG.)

Reli
25/05/26
Aditya Sawary

VAISHAL PATLIPUTRA DUGDH UTPADAK SAHKARI SANGH LIMITED

(Patna dairy Project)

Feeder Balancing dairy Complex, PHULWARISHARIF, Patna, 801505

(Phones: 2252553, 2252542, 2251622, Fax: 0612- 2250 325)

E-Mail -vpmu.engg@gmail.com

GST no - 10AAAAV8463B1ZV

SPECIAL CONDITION FOR THE WORK

_____ Nil _____

_____ Nil _____

1. No claim will be entertained due to idle labour and/any or and other cause.
2. levy cement if supplied by the Federation will be at the rate noted below :-
 - a. Cement _____ N.A _____
Place of delivery
_____ N.A _____
3. The contractor will have to provide huts for the laborers' at his own cost and will have to observe all labour rules including observance of the minimum labour waged.
4. After completion of work, the side of the work will have to be cleared off from all rubbish and un-used materials for which no extra payment will be made.
5. Time of completion of the work is (02) Two months from the date of issue of work order. However the contractor may quote his own line of completion.
6. The contractor employing motor vehicles should follow rules with regard to motor vehicles.
7. For excess consumption of the Federation materials over the actual requirement, recovery will be made at panel rate i.e. double of issue rate.
8. Only kiln burnt bricks will have to be used by the contractor in construction of work.
9. The contractor will be liable to pay compensation under the work-man's Act for accident or less of life, if any.
10. The contractor will be have to maintain site order book on the site of work exhibit able to inspecting officers any time on demand.
11. All works shall be carried out in workmanship like manner and as per standard specification of the VPMU/COMFED.
12. The authority reserves the right on distribution of work among several contractors.
13. Two percent (2%) Income Tax, 5% Security and Sales Tax/GST (Good Service Taxes) as per rule will be deducted from all payments (Gross amount).
14. The tenderers are presumed to have inspected the site and acquainted himself with the local condition of the work and no claim due to ignorance these conditions and also site conditions will be entertained.
15. No claim will be entertained for fluctuation of the rates of labour/materials and carriage at any stage of work under progress.
16. Items of work beyond agreement shall not be executed by the contractor, if this becomes a necessity, written order of Engineer In-charge should be obtained before taking up such

VAISHAL PATLIPUTRA DUGDH UTPADAK SAHKARI SANGH LIMITED

(Patna dairy Project)

Feeder Balancing dairy Complex, PHULWARISHARIF, Patna, 801505

(Phones: 2252553, 2252542, 2251622, Fax: 0612- 2250 325)

E-Mail -vpmu.engg@gmail.com

GST no - 10AAAAV8463B1ZV

works. Such items shall ordinarily be paid at schedule of rate. However, Contractor may prefer a claim before taking up such works and await decision of rates by the competent authority.

17. Quantity of work may increase or decrease in accordance with the order of E/I.
18. Contractor will assist supervision of work, measurement and verification of bills by the officers of the VPDUSS Ltd (VPMU) and will mend good any items damaged in course of inspection, measurement and verification of work.
19. Site shall be cleared and kept clean by the contractor at their own cost during completion of work.
20. Foundation trench shall have to be kept dry during the execution of work & de-watering can be ordered by the E/I if necessary.
21. Only ULTRATECH, LAFARGE, A.C.C PRISM, L & T & GRASIM cement will be used.
22. The bill will be submitted by the contractor once in a month for substantial quantity of work done. However, VPMU is not bound to make monthly payment for works considerably lower than warranted by the proportionate time.
23. Liquidated damages/ Delay penalty:- For delay in completion of the work beyond the stipulated completion time of two(02) months, a deduction at the rate of half percent (1/2 %) per completed week of delay day shall be made from your running account (RA) bills of those works which are completed beyond completion time of two (02) months. The penalty deduction under liquidated damage (LD) clause should not exceed 10 % (Ten Percent) at the total ordered / contract value.
24. Extension of time:- However, extension of the time for completion of the work, on the ground of having been unavoidably hindered in the execution of work OR on any other ground other than force majeure. Contractor may make request in writing to Managing Director/ Manager (Engg.) immediate after the date of start of the hindrance. It will be sole discretion of the Managing Director (VPMU) to grant time extension. If time extension is granted penalty deducted under LD clause will be refunded.

Reli
25/05/26

Manager (Engg.)

V.P.M.U, Patna