

VAISHAL PATLIPUTRA DUGDH UTPADAK SAHKARI SANGH LIMITED

PATNA DAIRY PROJECT

Feeder Balancing Dairy Complex, Phulwarisharif, Patna-801505

Ph: 0612- 2251622, 2252553, 2252542

Email Id.- vpmu.pur@gmail.com

VPDUSS-SOP-8.5.1.2-01.F02

DATE- 30.07.2026

PDP: PUR:HCC: 3332

Dear Sir,

We are interested for **Civil Construction Work of MS Structure Shed with Tata Steel Sheet Roofing for Retort Area for Flavoured Milk Section at Hajipur Dairy, Hajipur.**

Details scope of MS structure Shed work as follows-

1. Length ----- 7.121 Meters
2. Breadth ----- 7.969 Meters
3. Height ----- 3.048 Meters from the finished floor level.

Details work specification as per enclosed sheet

If party interested to work may submit the quotation in sealed envelope latest by **12.08.2026.**


Note:- Quotation validity for 30 days.

NOTE – Our payment terms is 100% after completion of work.

Delivery – Within 30 days.

Thanking You

Yours faithfully


Dy. Manager (MM)

CIVIL CONSTRUCTION WORK OF MS STRUCTURE SHED WITH MS COLUMN AND BRICK WORK FOR FLAVOUR MILK AT HAJIPUR DAIRY

Sl No.	Item Code	Description of Item	Unit	Length	Breadth	Depth	Qty
1	5.2.1	Sand	Cum				5.24
2		Bricks	Nos				7715
3		Cement	Bag				25
4		Mistri	Day				16
5		Labour	Nos				32
		Brick work in CM (1:6) on Madana flooring from three sides whose total approx length is 22 meter upto to 10 feet Height and breadth 0.23 meter with opening of 5.5 feet for entrance	Cum	22	0.23	3.05	15.43
9	5.9.1	Cement	Bag				7
10		Sand	Cum				0.36
11		Aggregate	Cum				0.72
12		Reinforcement Steel	kg				96
13		Mistri + Helpers					
14		Vibrator Operator					
15		CENTERING & SHUTTERING					
16		RCC column M20 with steel & shuttering at four corner of the wall to provide strength to the wall	Cum	0.3	0.23	3.05	4x0.2

17	5.18.1	Cement	Bag			
18		Sand	Cum			
19		Mason	sqm			
20		Helper	sqm			
22		Cement Plaster (12 mm thick) on both sides of wall	sqm	44		3.05
23	6.1.1	Oil Bound Distemper	L			
24		White cement (for primer)	kg			
25		Painter	sqm			
26		Helper	sqm			
28		Oil Bound Distemper (Interior)	sqm	44		3.05
29	6.3.1	Exterior Acrylic Emulsion	L			
30		Painter	sqm			
31		Helper	sqm			
33		Exterior Acrylic Emulsion	sqm	44		3.05

34	10.16	Structural Steel	kg	7.12	7.696	3.05
35		Cutting, welding, drilling	kg			
36		Erection (10 m height)	kg			
37		Red oxide + enamel	kg			
38		MS STRUCTURAL WORK (INCLUDING COLUMNS)	kg	7.12	7.696	3.05
39	12.5	MATERIAL	sqm	7.12	7.696	1.1
40		LABOUR + FIXING	sqm			
41		ACCESSORIES (J-bolts, washers, overlaps)	sqm			
42		TATA STEEL ROOFING SHEET/Roof Sheeting	sqm	7.12	7.696	1.1
43	12.52	Aluminium Whirlybird	Nos			
44		FIXING + LABOUR	Set			
46		WHIRLYBIRD VENTILATOR	Set			