

VAISHAL PATLIPUTRA DUGDH UTPADAK SAHKARI SANGH LTD

PATNA DAIRY PROJECT

Feeder Balancing Dairy Complex, Phulwarisharif, Patna – 801505

Phone – 0612-2252553, 2252542, 2251622, Fax-2250325

Email :- vpmu.pur@gmail.com

PDP: PUR: 7741

Dated: 17.03.2020

२)

SHORT TENDER NOTICE

Sealed Tender is invited from experienced party for **Civil work making base support for Installation of a new Cooling Tower beside evaporative Condenser, FBD Patna**. The details scope of work is attached herewith as per **BOQ**.

Interested parties may submit their quotation latest by 31.03.2020 by 5.00 pm in sealed envelope addressed to Managing Director, VPDUSS Ltd., Patna super scribing on the top of the envelope Tiles **"Cooling Tower beside evaporative Condenser, FBD Patna"**.



Manager (MM)

Enclosure: As above

Note: 1) The rate should be all inclusive FOR FBD
2) All the legal document i.e. Photo, ID Proof
Service Tax papers, etc (Xerox is to be enclosed)

CC: Notrice Board, FBD, CFF, HCC
Patnadairy.org

Bill of Quantities(BOQ)

**WORK:- Civil work in making base support for installation of a new cooling tower beside
evaporative condenser**

SOR 2018	NAME OF WORK	UNIT	QTY.	RATE	AMOUNT
p-249/20.2.2	Boring,providing and installing bored cast-in-situ reinforced cement concrete piles of grade M-25 of 400mm dia. piles and length below the pile cap, to carry a safe working load not less than specified,excluding the cost of steel reinforcement but including the cost of boring ,with bentonite solution and temporary casing of appropriate length for setting out and removal of same and the length of the pile to be embedded in the pile cap etc. all complete , including removal of excavated earth with all lifts and leads(Length of the pile for payment shall be measured upto bottom of the pile cap).	m	1.5	1110.8	1666.200
p-249/20.2.1	Boring,providing and installing bored cast-in-situ reinforced cement concrete piles of grade M-25 of 300mm dia. piles and length below the pile cap, to carry a safe working load not less than specified,excluding the cost of steel reinforcement but including the cost of boring ,with bentonite solution and temporary casing of appropriate length for setting out and removal of same and the length of the pile to be embedded in the pile cap etc. all complete , including removal of excavated earth with all lifts and leads(Length of the pile for payment shall be measured upto bottom of the pile cap).	m	18	838.1	15085.800
P-153/11.72	Earth work in surface excavation for all type of soil not exceeding 30 cm in depth but exceeding 1.5m in width as well as 10 sqm on plan including disposal of excavated earth upto 50 m and lift upto 1.5 m .Disposed soil to be leveled and neatly dressed	SQM	2.075	40.84	84.743
P-153/11.72	providing designation 100A one brick FLAT soling joints filled with local sand including cost of watering, taxes,royalty all complete as per building specification and direction of E/I	SQM	17.275	277.5	4793.813

P-83/5.1.2	Providing and laying in position 1:1.5:3(1 cement :1.5 coarse sand :3 graded stone aggregate 20mm nominal size) in plateform and floor base excluding the cost of centering,shuttering,finishing and reinforcement upto plinth level	CUM	1.592	4902.3	7804.462
P-87/5.33A.2.1	Providing and laying in position machine batched,machine mixed and machine vibrated design mix cement concrete of M20 grade with 1:1.5:3(1 cement :1.5 coarse sand :3 graded stone aggregate 20mm nominal size)in tie beam,columns and pile caps excluding the cost of centering,shuttering,finishing and reinforcement upto plinth level	CUM	2.22	5373.1	11928.282
P-167/13.12.4	15 mm cement plaster 1:6(1 cement : 6 coarse sand) on exterior of partition wall	SQM	16	145.5	2328.000
P-167/13.24.2	6mm cement plaster to ceiling of mix 1:4(1 cement :4 coarse sand)	SQM	39.3	110.9	4358.370
P-167/13.26	Neat cement punning	SQM	55.3	38.6	2134.580
P-86/5.22	Reinforcement for RCC work including straightening,cutting,bending,placing in position and binding all complete				
P-86/5.22.7A	TMTC-500-8 mm bars	Kg	158.11	77.4	12237.714
P-86/5.22.7B	TMTC-500-10 mm bars	Kg	18.6	76.7	1426.620
P-86/5.22.7C	TMTC-500-12 mm bars	Kg	233.36	75.2	17548.672
P-84/5.9	CENTRING AND SHUTTERING including strutting,propping etc. And removal of form for Columns AND pile caps				
P-84/5.9.3	For plateform slab	SQM	3.170	362.6	1149.442
P-84/5.9.6	For columns	SQM	24.960	425.8	10627.968
P-84/5.9.5	For lintels,beams and bands	SQM	9	335.3	3017.700
Details attached	Carriage charge		Rs		17735.651
TOTAL ESTIMATED COST=					113928.016
TOTAL ESTIMATED COST(SAY)=					113928

Rs One Lakh Thirteen Thousand Nine Hundred Twenty Eight only

I AGREE & READY TO DO THIS WORK

1.0	ON THE GIVEN B.O.Q RATE	%	
2.0	ABOVE THE B.O.Q RATE(PRESENT)	%	
3.0	BELOW THE B.O.Q RATE(PRESENT)	%	

Signature of client

Signature of contractor