

VAISHAL PATLIPUTRA DUGDH UTPADAK SAHKARI SANGH LTD

# PATNA DAIRY PROJECT

Feeder Balancing Dairy Complex, Phulwarisharif, Patna – 801505

Phone – 0612-2252553, 2252542, 2251622, Fax-2250325

Email :- vpmu.pur@gmail.com

PDP: PUR: 7093

Dated: 19.02.2020

## SHORT TENDER NOTICE

Sealed Tender is invited from experienced party for **Civil Construction of foundation for Cooling Tower on the roof of Ice cream Plant, FBD, Patna**. The details scope of work is attached herewith as per Annexure –I.

Interested parties may submit their quotation latest by 05.03.2020 by 5.00 pm in sealed envelope addressed to Managing Director, VPDUSS Ltd., Patna super scribing on the top of the envelope Tiles **“foundation for Cooling Tower on the roof of Ice cream Plant”**.

  
Manager (MM)

Enclosure: As above

Note: 1) The rate should be all inclusive FOR FBD  
2) All the legal document i.e. Photo, ID Proof  
Service Tax papers, etc (Xerox is to be enclosed)

CC: Notrice Board, FBD, CFF, HCC  
Patnadairy.org

**Civil construction of foundation for Cooling tower on the roof of  
Ice cream plant, FBD, Patna**

	NAME OF WORK	UNIT	QTY.
1	Demolishing cement concrete(chipping) of 1:3:6 or richer mixes including disposal of unserviceable material within 50 meter lead at roof	CUM	1.226
2	Providing and laying in position machine batched, machine mixed and machine vibrated design mix cement concrete of M-20 grade with 1:1.5:3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate) excluding the cost of centering, shuttering, finishing and reinforcement above plinth level In.	CUM	3.173
3	15 mm cement Plaster 1:6 (1 Cement: 6 coarse sand) on exterior of partition wall	Sqm	30
4	Reinforcement for RCC work including straightening, cutting, bending, placing in position and binding complete		
	TMTC-500 – 8mm bars	Kg	91.29
	TMTC-500 – 12 mm bars	kg	159.49
5	For Colomns	Sqm	16.200
6	For Tie Beams	Sqm	6.000