

VAISHAL PATLIPUTRA DUGDH UTPADAK SAHKARI SANGH LTD

PATNA DAIRY PROJECT

Feeder Balancing Dairy Complex, Phulwarisharif, Patna – 801505

Phone – 0612-2252553, 2252542, 2251622, Fax-2250325

Email :- vpmu.pur@gmail.com

PDP: PUR: 1374

Dated: 31.05.2023

TENDER NOTICE

Sealed Tender is invited from experienced party for Work for **making provision of power capacitors with controller in the old & unused sub LT panel near main LT panel and Power transformer in the CFP for improving power factor.** The details scope of work attached herewith as per BOQ.

Interested parties may submit their quotation latest by 15.06.2023 by 5.00 pm in sealed envelope addressed to Managing Director, VPDUSS Ltd., Patna super scribing on the top of the envelop Tiles "**Power capacitors with controller at CFP**".

Bidder must be registered for civil work in Bihar Govt or COMFED, Patna.



Manager (MM)\

Enclosure: As above

Note: 1) The rate should be all inclusive FOR FBD
2) All the legal document i.e. Photo, ID Proof
Service Tax papers, etc (Xerox is to be enclosed)

CC: Notrice Board, FBD, CFF, HCC
Patnadairy.org

BILL OF QUANTITY

Work :For making provision of power capacitors with controller in the old & unused sub LT panel near main LT panel & p power transformer in the CFP for improving power factor.

Sl No	Description of works to be done	Qty	Rate to be quoted by tenderer (In Rs)
1	Dismantling of damaged components of old LT panel near main LT panel & transformer along with old & damaged HT switch Gear panel by the side of old & damaged LT panel. Complete with all labour, tools & tackles.	One job complete	
2	Repairing, cleaning & painting of both old LT panel & damaged HT switch Gear panel complete with all labour tools & tackles, paint will be provided by CFP.	One job complete	
3	Providing & fitting MS racks with welding so as to make it suitable for keeping power capacitor & controller. Complete with all labour, tools & tackles .Capacitors & controllers will be provided by CFP.	One job complete	
4	Capacitors & capacitor panel wiring and connection with outgoing switch gears in Main LT panel.	One job complete	
5	Swith gear fitting work complete with all labour only.	One job complete	
6	Finall installation & Commissioning of the power capacitor panel to ensure overall power factor to be not less than - 0.95/ 0.96.	One job complete	
7	Cleaning & painting outsides only of main LT panel just near the main transformer.	One job complete	
8	Total		
9	Applicable GST @ of ----- %		
10	Grand Total price quoted		
11	Name & address of tenderer with Email		
12	GST no		

In words:-

Signature with seal of tenderer